BUILDERS CONCRETE SERVICES, LLC
321 Center Street, Hillside, IL 60162
P: 708.432.0576
F: 708.544.0230

TO: **VILLAGE OF ROMEOVILLE**

Project: **JJC NEW SIDEWALK INSTALL**
Location: 135TH STREET ROMEOVILLE, IL
Date: 7-8-2026
Est.: Chuck Fitzgerald
Scope: EXCAVATION, STONE, CURB, PCC SIDEWALK
Job No:
Print:
Add:

	Description	Quantity	UM	UP	TOTAL
	SCOPE				
1	MOBILIZATION - 663 - TRAFFIC CONTROL	1.00	EA	$11,000.00	$11,000.00
2	EXISTING CURB REMOVAL	65.00	LF	$29.00	$1,885.00
3	CONCRETE CURB - TYPE B6.12 HAND W/(2) #4 CONT	65.00	LF	$61.00	$3,965.00
4	EXISTING SIDEWALK REMOVAL	141.00	SF	$5.00	$705.00
5	EARTH EXCAVATION 9" AND HAUL OFF	150.00	CY	$95.00	$14,250.00
6	AGGREGATE BASE 4" NEW SIDEWALK ONLY	4,813.00	SF	$2.25	$10,829.25
7	SIDE CURB	136.00	LF	$28.00	$3,808.00
8	5" SIDEWALK W/6X6-1.4 WWF	4,813.00	SF	$11.00	$52,943.00
				TOTAL:	**$99,385.25**

SPECIFIC INCLUSIONS:
FLAGGERS
TRAFFIC CONTROL
HAUL OFF OF SPOILS (NON SPECIAL WASTE)
BID FOR SINGLE MOBILIZATION
663

WINTER SERVICE *(when applicable)*

HOT WATER: $18.00 PER YARD
NCA @ 1%: $12.00 PER YARD
NCA @ 2%: $24.00 PER YARD
WINTER BLANKET RENTAL - $65.00 PER BLANKET + INSTALLATION & REMOVAL LABOR

SPECIFIC EXCLUSIONS:

1. HOT POUR JOINT SEALER
2. EXCAVATION UNDERCUTS
3. P&P BONDS
4. INLET PROTECTION
5. JOINT SEALANT OR CAULK FOR CONTROL, CONSTRUCTION OR EXPANSION JOINTS IN PAVEMENT
6. MULTIPLE MOBILIZATIONS
7. REMOVAL AND HAULING OF SPECIAL WASTE OR CONTAMINATED SPOILS
8. SIGNAGE REMOVAL AND RELOCATION
9. STRIPING
10. TREE REMOVAL
11. SURVEYING FOR LAYOUT
12. ASPHALT PATCH
13. ADA TILES (TO BE PROVIDED BY OTHERS)

CHUCK FITZGERALD - PM

ACCEPTED BY:_____ DATE:_____