



25 FORESTWOOD DRIVE * ROMEOVILLE, IL 60446
(815) 886-0400 * FAX (815-886-0455)

September 11, 2019

Revised

Village of Romeoville

Att: Mike Littrell
Email: mlittrell@romeoville.org

From: Dan Tiberi

Ref: **REMA Slab on grade
Romeoville, IL**

PAGE 1 OF 2

We propose to furnish labor, material and equipment as it applies to the concrete scope of work for the above referenced project.

Work to be in accordance with the drawings dated N/A and the below listed items.

Building:

*Main Slab on grade, 5" & 6" w/7.5 lbs./cy Strux 90/40 Macrofibers, vapor barrier
Thickened edge
Trench Train (ACO), furnished and installed by others.
Dowel to existing floor slab at 4' x19'-6" area*

Main slab on grade Total:

\$35,500.00

**Ref: REMA Slab on grade
Romeoville, IL
Martin Cement Company**

PAGE 2 OF 2

Exclusions:

- 1 Sales Tax
- 2 Saw cut, demolition, removal and haul away by others
- 3 Excavation and backfill
- 4 Granular fill
- 5 Performance bond
- 6 Moist or wet cure
- 7 Site work
- 8 Mechanical & Electrical Concrete
- 9 Winter/weather protection
- 10 Icing/cooling of concrete due to extreme heat
- 11 Floor sealers or hardeners
- 12 Pumping of ground water
- 13 Dust protection
- 14 Frost cutting
- 15 Welding of rebar
- 16 Traffic control
- 17 Barricades
- 18 Corrosion inhibiting admixtures
- 19 Temporary heating
- 20 Joint sealers
- 21 Winter service ready-mix 11-1-19 through 3-31-20
- 22 June 1, 2020 labor increase
- 23 January 1, 2020 ready-mix increase
- 24 MBE/WBE minority participation
- 25 Female labor requirements
- 26 Additional concrete for poor soils
- 27 Permits
- 28 Engineering layout
- 29 Epoxy coated reinforcement

*** Unless otherwise noted, this price is good for thirty (30) days from the date of this proposal. Martin Cement's obligation to perform the work referred to in this proposal is subject to negotiation of an acceptable contract, the approval and acceptance of which is subject to our sole discretion.**

Respectively submitted,

**Daniel C. Tiberi
Martin Cement Company**