

PEERLESS FENCE

A Division of Peerless Enterprises, Inc.
33 W 401 Roosevelt Road * West Chicago, IL 60185
(630) 584-7710 * Fax (630) 584-7746

**PROPOSAL AND
ACCEPTANCE****REVISED**

Attn: Al Grzyb		Phone: (815) 886-6222	Date: 6/11/2018
Proposal submitted to: Village of Romeoville		Fax: (815) 886-6245	Job Phone:
Street: 900 West Romeo Road		Job Name: Various Repairs	
City, State and Zip Code: Romeoville, IL 60446		Job Location: Romeoville, IL	
Architect	Date of Plans		

We hereby submit specifications and estimates: Furnish and Install

Village Park Field #5:

Remove and replace one (1) terminal post for 6' high fence (existing post has heaved)

Specifications:

Remove existing post/footing and haul from site

2 7/8" SS-40 galvanized post, set in a 12" x 42" concrete footing

Re-use existing fence fabric and fittings

Total \$985.00

Village Park Field #2:

Option #1: Attempt to lower fence fabric on backstop

Remove and replace six (6) terminal posts for 4' high fence, three (3) posts for 8' high fence (existing posts have heaved) and knock down footings on existing backstop and attempt to lower existing fence fabric

Specifications:

Remove existing posts/footings and haul from site

2 3/8" SS-40 galvanized posts, set in a 10" x 42" concrete footing (4' high posts)

2 7/8" SS-40 galvanized posts, set in a 12" x 42" concrete footing (8' high posts)

Knock down existing backstop post footings

Attempt to lower vertical fence fabric to keep balls from going under fence

Re-use existing fence fabric and fittings

Total \$6,950.00

Volunteer Park:

Cut down up to twenty-two (22) posts and lower fence fabric in high areas on two (2) outfield fences

Specifications:

Cut down existing posts to attempt to keep top rail level as well as possible

Re-tie existing fence fabric to existing framework

Total \$4,900.00

Discovery Park:**Enclosure #1:**

38' of 6' high black vinyl chain link fence, including one (1) 7' opening x 6' high double drive gate

Specifications:

2" mesh x 9 gauge core/8 gauge finish fused bonded black fence fabric

1 5/8" SS-40 black top rail

1 7/8" SS-15 black gate frame

2 3/8" SS-40 galvanized line posts, set in a 10" x 36" concrete footing

2 7/8" SS-40 galvanized corner and gate posts, set in a 12" x 42" concrete footing

Bulldog style hinges and double drive gate latch for gate hardware

Total \$5,450.00

Enclosure #2:

112' of 6' high black vinyl chain link fence, including one (1) 10' opening x 6' high double drive gate

Specifications:

2" mesh x 9 gauge core/8 gauge finish fused bonded black fence fabric

1 5/8" SS-40 black top rail

1 7/8" SS-15 black gate frame

2 3/8" SS-40 galvanized line posts, set in a 10" x 36" concrete footing

2 7/8" SS-40 galvanized corner and gate posts, set in a 12" x 42" concrete footing

Bulldog style hinges and double drive gate latch for gate hardware

Total \$8,300.00

Boucher Prairie Park:

Backstop Repair:

Remove and replace back center backstop fence fabric, replace one (1) tension bar and add one (1) middle rail in back center of backstop

Specifications:

2" mesh x 6 gauge core/5 gauge finish fused bonded black fence

1 5/8" SS-40 black middle rail

Total \$2,200.00

Roller Hockey Fence:

Replace approximately 100' of 4' high fence fabric at roller hockey fence and add approximately 40' of additional rail to existing framework

Specifications:

2" mesh x 6 gauge aluminized fence fabric

1 5/8" SS-40 galvanized rail

Total \$3,985.00

GRAND TOTAL \$32,770.00

Proposal Based on:

Full day mobilizations

Spoils spread along fence line or stock piled on site

Normal digging conditions

Peerless standard safety requirements

Peerless standard insurance

Specifications & Quantities above

Able to access fence line with digging equipment & cement truck

Fence line established by others

Private utilities located by others

Prices good for 15 days

Quoted price is based on the current market conditions. We reserve the right to adjust this quote based on market conditions at the time material is ordered and delivered to the job site.

Exclusions: Bonds, permits, licenses, and fees

Work performed on a regular time basis per our current certificate of insurance

Payment to be made as follows: net 30 days on completion, upon credit approval.

OWNER MUST OBTAIN ALL PERMITS.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner, on a regular time basis according to standard practices. Any alternation or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tomado and other necessary insurance. Our workers are fully covered by Workmen's Compensation Insurance. Customer here by assumes full responsibility for the location of the line upon which fence materials are to be installed and locate any and all private cable to include sprinkler systems, electric, septic fields, gas lines, grills, lighting, etc. Peerless Fence to Call J.U.L.I.E.

Authorized Signature:

Brad Knepper

Brad Knepper, Commercial Sales

PEERLESS FENCE

Note: We may withdraw this proposal if not accepted within 15 days.

I, THE UNDERSIGNED, HEREBY AGREE THAT IN THE EVENT OF DEFAULT IN THE PAYMENT OF ANY AMOUNT DUE, AND IF THIS ACCOUNT IS PLACED IN THE HANDS OF AN AGENCY OR ATTORNEY FOR COLLECTION OR LEGAL ACTION, TO PAY AN ADDITIONAL CHARGE EQUAL TO THE COST OF COLLECTIONS INCLUDING AGENCY AND ATTORNEY FEES AND COURT COSTS INCURRED AND PERMITTED BY LAWS GOVERNING THESE TRANSACTIONS. ALL PAST DUE ACCOUNTS WILL BE CHARGED AT THE RATE OF 1.5% ON UNPAID MONTHLY BALANCE.

ACCEPTANCE OF PROPOSAL. The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified.

Payment will be made as outlined above.

Date of Acceptance _____

Signature _____

Signature _____