

Task Order No. 26-02
Village of Romeoville, Illinois (OWNER)
and Robinson Engineering, Ltd. (ENGINEER)
Pursuant to Technical Services Agreement dated January 1, 2017

Project Information

Services Name: 2026 SSES – Basins 2 & 2A (Smoke Testing). (Ref. REL Project 26-R0115.02)

Services Description: The OWNER requests the ENGINEER to perform engineering services related to sanitary sewer evaluation services including smoke testing and program management. The overall goals of the project will be to identify and reduce infiltration and inflow and to restore structural integrity in the system.

Scope of Services

ENGINEER will provide the following services to OWNER:

1. Project Kickoff
 - a. REL will schedule a project kickoff meeting with the Village to discuss project scope, establish lines of communication, and to set the project schedule.
 - i. Throughout the project, REL will communicate to the Village when crews will be onsite for smoke testing through daily emails and phone calls.
 - b. Setup the online GIS digital data dashboard for access to field collected data and photos.

2. Smoke Testing – Basins 2 & 2A
 - a. Draft mailer for smoke testing (The Village to mail out the letters)
 - b. Equipment and Personnel to smoke approximately 123,864 LF of sewer
 - c. Online ArcGIS dashboard viewer
 - d. Smoke testing summary report
 - i. List of defects by address
 - ii. Digital photos of each defect
 - iii. GPS locations of each defect with exhibits
 - iv. Cost estimates for repair of the defects
 - v. Estimated I/I removal
 - vi. Defect summary - \$/ estimated GPM of I/I removed

Compensation

Smoke Testing	\$144,920
Project Management	<u>\$3,750</u>
Total	\$148,670

{LUMP SUM}

OWNER shall compensate ENGINEER for “Project Management” Services under this Task Order on a lump sum basis for \$3,750.

{UNIT PRICE}

OWNER shall compensate ENGINEER for “SSES” Services including Smoke Testing under this Task Order on a unit price basis per the attached rate schedule for an estimated fee of \$144,920.

Schedule

Services will begin upon execution of this Task Order, which is anticipated for (+/- May 20, 2026). Schedule for the services are as follows:

- Kickoff meetingJuly 1, 2026
- Smoke Test Mailers.....July 15, 2026 – August 1, 2026
- Smoke Testing.....August 17, 2026 – September 30, 2026
- Analyze data.....October 1, 2026 – December 31, 2025
- Submit preliminary findings report for review / commentsDecember 31, 2026
- Submit final reportJanuary 29, 2027

TASK ORDER AUTHORIZATION AND ACCEPTANCE:

ENGINEER:

OWNER:

ROBINSON ENGINEERING, LTD.

VILLAGE OF ROMEOVILLE

 Joel Drabicki, CFM Date
 Senior Engineer

 Chris Drey Date
 Director of Public Works

Romeoville Project Number: _____

Romeoville Account Number: _____