

<b>Attention:</b> Ken Kroll	<b>Project:</b> Romeoville Police Department
<b>Company:</b> Romeoville Police Department	<b>Address:</b> 1050 West Romeo Road
<b>Address:</b> 1050 West Romeo Road	<b>City, State:</b> Romeoville, IL
<b>City, State:</b> Romeoville, IL	<b>Architect:</b> n/a
<b>Phone:</b>	<b>Plan Date:</b> n/a
<b>Mobile:</b> 815-693-3423	<b>Sheets:</b> n/a
<b>Email:</b> <a href="mailto:kkroll@romeoville.org">kkroll@romeoville.org</a>	<b>Specs:</b> n/a
	<b>Addendum:</b> n/a

**Furnish and install the following:**

- 1) Remove existing 1" IG units and install new Level 3 (approximately 1.125" thick) clear bullet resistant polycarbonate glazing at a total of 15 first floor lites per site visit.
- 2) New glass will be installed into existing non-BR rated storefront frame and caulked into place.
- 3) Alliance Glazing Technologies will require sign-off if this option is taken that the existing framing is NOT bullet resistant and we are not held responsible for damages caused if the framing is shot through.

**FOR THE LUMP SUM OF**

**\$29,200**

**Sales tax is included. NOTE: This price is valid for 30 days from the date of this proposal.**

**Exclusions:**

- 1) Final cleaning
- 2) Payment/performance bond
- 3) Sales tax
- 4) Attic and/or extra stock
- 5) Material protection (i.e. Blue Max, Polystyrene, Cardboard)
- 6) OT premium

**Jim Zorn**

Regional Pre-Construction Manager  
[jimzorn@allianceglazing.com](mailto:jimzorn@allianceglazing.com)

**Chris Deckinga**

Senior Estimator  
[chrisdeckinga@allianceglazing.com](mailto:chrisdeckinga@allianceglazing.com)

ROMEDEVILLE POLICE  
1050 WEST ROMEO ROAD  
ROMEDEVILLE IL 60446

PHASE 2  
MEASURED MAY 22, 2019



41 8'10" X 24 17'10" GLASS SITE  
●●●●● FIVE LITERS ●●●●●  
12 LITERS

42 1'4" X 54 1'56" GLASS SITE  
CENTER LITERS  
(2) LITERS

Second Replacement Phase

15  
total

