



1410 Mills Road • Joliet, Illinois 60433 • T (815) 774-0350 • F (815) 774-0352 • www.georgeslandscaping.com

4/17/2018

Kelly Rajzer
Director of Parks and Recreation
Village of Romeoville Parks and recreation Department
900 West Romeo Road
Romeoville, IL 60446

RE: Deer Crossing Park Proposal #2
1050 W Romeo Road

Kelly,

I am pleased to quote the following work for the sitting area at the Deer Crossing Park Area as we discussed at our site meeting on 4/10/2018. Following is the work that GLI will complete in the existing area of the playground which houses the Dance Chimes and the Super Nova Play Piece.

Concrete Mud Slab under Belden Clay Pavers

GLI to include all additional excavation to excavate existing base area approx. 5" lower than existing. The existing CA6 base will be moved and the soil sub base will be cut by 5" and the spoils will be hauled off and disposed of. The CA6 materials will be transferred back to the area and spread. GLI will add about 1.5" of new CA6 and compact the area to ready for the installation of a 4" concrete slab. GLI will pour 1150 S.F. of 4" concrete pad and will finish with a light broom finish. The paver sand can now be spread and the rest of the paver work completed.

Pricing for the Excavation and 4" Concrete Slab.....\$10,714.00

Excavation and 6"x12" Concrete Curbing Banding

(Area of work to be completed is between the two seat walls which edge the area with the net climbers and the new patio area.)

Cut back the existing rubber surfacing on the net climber side to create a clean edge for the curbing to be constructed.

Excavate a curved area approx. 18 L.F. from seat wall to seat wall. The area will keep the shape of the curves on the existing seat walls.

Frame and pour a new paver edge curb, 6"x12"x18', from seat wall to seat wall. The curb will be level with the surface of the new pavers. This curb will service as the boarder or edge of the pavers at this location.

Price for Excavation and Concrete Curbing.....\$2100.00

Paver Brick Work

The existing CA6 base will be graded and compacted.

8 tons of mason Sand will be brought in and spread at 1" in depth.

The paver base will be leveled and keep smooth.

Purchase and Install approx. 1150 S.F. of Belden Holland Clay Pavers and the sand base.

The edge / perimeter of the area will have the Holland Pavers installed as a soldier coarse.

The body of the patio will have the pavers install on a 45 degree herringbone pattern.

The paver type and color will match the body of the paver area by the band shell.



Once the pavers area all in place the paver area will have approx. 600 lbs. of beige poly sand swept into the joints to lock the pavers together.

Paver area will be compacted by running a lite vibrating compactor over the surface.

Paver Work Price.....\$22,695.00

Total Project Cost for this Proposal.....\$35,509.00

Exclusions:

Construction Fencing Around Playground and Patio Area
Portable Toilet
Dumpster for Vitriturf
Permits
Site Clean Up and Security for Vitriturf

Pricing Good for 15 Days from the Date of Issue.....

Proposal Accepted By:_____Title:_____

Date:_____

Sincerely,

A handwritten signature in black ink, appearing to read 'G. Petecki, Jr.', with a stylized flourish at the end.

George Petecki, Jr.
President