

Engineer's Opinion of Probable Cost - Erosion Control

12/14/2020

214 S. Pinnacle Drive, Romeoville, Illinois

Site Engineering Improvements - Truck Parking Lot Addition

Item No.	Description	Unit	Estimated Quantity	Estimated Unit Cost	Estimated Amount
1	TRAFFIC CONTROL, CONSTRUCTION BARRIERS, TEMPORARY FENCING	LUMP	1	\$ 5,000.00	\$5,000
2	MISCELLANEOUS EROSION CONTROL MEASURES	LUMP	1	\$ 2,500.00	\$2,500
4	PERIMETER EROSION BARRIER, SILT FILTER FENCE [Sec. 280]	L.F.	1,260	\$ 5.00	\$6,300
5	LEVEL SPREADER, 24" WIDE	L.F.	504	\$ 20.00	\$10,080
8	SEEDING [Sec. 250]	S.Y.	170	\$ 10.00	\$1,700
9	EROSION CONTROL BLANKET, EXCELSIOR BLANKET [Sec. 251]	S.Y.	170	\$ 5.00	\$850
				TOTAL	\$26,430

Notes:

- (1) Haul costs are understood to be included in all unit quantities.
- (2) LEVEL SPREADER includes full installation per plan details.